

“स्वच्छ, सफा, समृद्ध, सुन्दर - महालक्ष्मी नगर”
"Clean, Green, Prosperous, Full of Beauty - Mahalaxmi Municipality"



महालक्ष्मी नगरपालिका Mahalaxmi Municipality नगर कार्यपालिकाको कार्यालय Office of the Municipal Executive

पत्र संख्या (Let. No.):
चलानी नं. (Reg. No.):

ललितपुर, बागमती प्रदेश, नेपाल
Lalitpur, Bagmati Province, Nepal



सूचना प्रकाशन मिति: २०८२-०७-२३

आर्थिक प्रस्ताव पेश गर्ने सम्बन्धी ७ (सात) दिने सूचना

महालक्ष्मी नगरपालिका वडा नं. ९ स्थित घिमिरेथोक राधाकृष्ण मन्दिर हुदै गैही गाँउ जाने सडक तथा लुभुखोला नेपाल चौर जाने सडकको खोलाको वाल लगाउने कार्यको लागि सार्वजनिक खरिद नियमावलीको दफा ८५ बमोजिम यस कार्यालयमा सूचिकृत निर्माण व्यवसाईहरुबिच प्रतिस्पर्धा गराई निर्माण व्यवसाई छनौट गर्नु पर्ने व्यस्था भएकोले उक्त कार्यका लागि सार्वजनिक खरिद नियमावलीको नियम १० बमोजिम तयार गरिएको करसहितको जम्मा लागत अनुमान रु. ६,१९,४७६।८० (भ्याट सहित) भन्दा नबढ्ने गरी कुल लागत सहितको आर्थिक प्रस्ताव खामबन्दी गरि आजको मितिले ७ दिनभित्र यसै सूचना साथ संलग्न BOQ अनुसार नगरपालिकाको कार्यालयमा पेश यो सूचना प्रकाशन गरिएको छ।

सुवन महर्जन
इन्जिनियर
सुबर्ण लुभुखोला
ने.इ.प.न. २०७२ सिमिल 'क'

फोन: ०१-५२०३५९२, ०१-५२०१६३३, ०१-५२०१७३३

Email: info@mahalaxmimun.gov.np, mahalaxmimun@gmail.com, Web: <http://mahalaxmimun.gov.np>

नगर कार्यपालिकाको कार्यालय
कमलपोखरी, ललितपुर
बागमती प्रदेश, नेपाल
Bill of Quantities

योजनाको नाम: विभिन्न राधाकृष्ण मन्दिर हुदै गौरी गाँउ जाने सडक + लुभुखोला नेपाल चैर जाने सडकको खोलाको बाल

आ.व. २०८२/८३

वडा नं. ९

S.No.	Description of work	Unit	Quantity	Rate in Figure	Rate in Words	Total Amount
1	Roadway excavation in all type of soil including disposal of excavated material at approved environmentally safe tipping sites, etc. all complete as per specification by mechanical means [SS 905]*	cum	93.59			
2	Providing mechanically woven double twisted gabion boxes/crates /mattress with diaphragm including rolling, cutting and with lacing wire of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvaige wire 3.9 mm, lacing wire 2.4 mm; assembling Gabion boxes mattresses, placing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, bedding, bonding and all transportation as per specification. [SS 2402]*	Cum	59.50			
3	Providing suitable material and Back filling behind abutment with Local available material	cum	42.00			
4	Providing and laying of Random Rubble Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications.	Cum	8.72			
5	Providing and laying of Plain Cement Concrete grade M15 in Foundation including formwork etc. all complete as per Drawing and Technical Specifications.	Cum	2.75			
18						
				Total Construction cost (A)		
				VAT (B)=13% of A		
				Total Construction cost (A+B)		